23 July 2003

MEMORANDUM FOR THE CHIEF OF STAFF, COMBINED JOINT TASK FORCE 7

FROM ADMINISTRATOR, COALITION PROVISIONAL AUTHORITY

SUBJECT: Tasking Letter – 3204-301 VSAT Installation Site Preparation Information and Guidance

Reference: Request from the Ministry of Transportation and Communications

I request that the Commander, Combined Joint Task Force 7 take the appropriate action to provide guidance and information to the Airfield Commanders at Kirkuk, Mosul, and Ar Rutbah on the installation requirements for the VSAT Air Traffic Control Equipment.

WHO: Airfield Commanders at Kirkuk, Mosul and Ar Rutbah

WHAT: Provide the following information. Commanders need to select a space that has the following requirements:

- 1) Dustproof and preferably and air conditioned space for one rack with a 600mm Wide x 900mm Deep footprint at non RCAG sites and space for two racks, each with a 600mm Wide x 900mm Deep footprint at RCAG sites.
- 2) Dustproof and preferably air conditioned space for a battery rack with a 1500mm x 1500mm footprint and access to three (3) sides.
- 3) Wall space adjacent to the battery rack for mounting charging and control equipment.
- 4) External space, no more than 50 meters distance from the equipment room, for a 2.4 meter VSAT antenna with a footprint of 5200mm square and a clear horizon between 90 and 130 degrees true bearing.
  - 5) Clear out installation area prior to arrival of installation team.
  - 6) Select an alternate site.

WHERE:

WHEN:

KIRKUK MOSUL

27 - 29 JUL

AR RUTBAH

On or about 5 AUG

On Order

Direct coordination between the tasked unit(s) and the CPA representative listed below is requested.

The point of contact for this request is. (b)(2),(b)(3):10 USC §130b,(b)(6)
(b)(2),(b)(3):10 USC §130b,(b)(6)

The Requirements Coordination Office (RCO) point of contact is (b)(2),(b)(3):10 USC §130b, (b)(2),(b)(3):10 USC §130b,(b)(6)

Patrick Kennedy Chief of Staff