UNCLASSIFIED



UNITED STATES CENTRAL COMMAND OFFICE OF THE COMMANDER 7115 SOUTH BOUNDARY BOULEVARD MACDILL AIR FORCE BASE, FLORIDA 33621-5101



16 February 2016

MEMORANDUM FOR SECRETARY OF DEFENSE CHAIRMAN, JOINT CHIEFS OF STAFF

FROM: General Lloyd J. Austin III, Commander, U.S. Central Command

SUBJECT: Emergency and Extraordinary Expense Request - Kunduz Hospital (U)

Mr. Secretary, Chairman,

The purpose of this memo is to endorse the request (TAB A) of Commander, United States Forces - Afghanistan (USFOR-A) for \$5,790,349 in Emergency and Extraordinary Expense (EEE) authority to reconstruct the heavily-damaged hospital in Kunduz, Afghanistan.

BACKGROUND

- On 3 October 2015, U.S. combat activity in Kunduz, Afghanistan damaged a building owned by the Government of the Islamic Republic of Afghanistan (GIRoA). The building was being used as a hospital at the time it was damaged.
- The hospital building is owned by the GIRoA's Ministry of Commerce and Industries (MoCI) through the state-owned Spinzar Corporation. The GIROA has requested that USFOR-A return the facility to its condition prior to the 3 October 2015 strike.

DISCUSSION

- The U.S. Army Corps of Engineers (USACE) conducted a damage assessment of the building and determined the facilities ground floor is a total loss and the basement is considered repairable. The current working estimate by USACE to reconstruct the structure is \$5,790,349.
- All authorities and funding sources available to USCENTCOM have been reviewed. It is determined that only the Commander's Emergency Response Program authority under Section 1200 of the Fiscal Year 2016 National Defense Authorization Act is legally available for the hospital reconstruction. However, this fund is limited to a \$2M cap.
- EEE is an authority, which may be used by the Secretary of Defense or Secretaries of the Military Departments, to fund any emergency or extraordinary expense which cannot be anticipated or classified. The funds requested cover only the restoration of the facility itself, not any of the medical equipment owned by MSF.

UNCLASSIFIED

UNCLASSIFIED

RECOMMENDATION

 Approve \$5,790,349 in Secretary of Defense EEE authority to be issued to USACE or direct Service EEE authority be used for the reconstruction of the hospital in Kunduz, Afghanistan.

Attachment:

TAB A: 24 January 2016 USFOR-A Memorandum to the USCENTCOM Commander

Copy to: OSD Comptroller Joint Staff Comptroller

UNCLASSIFIED



UNCLASSIFIED HEADQUARTERS UNITED STATES FORCES-AFGHANISTAN KABUL, AFGHANISTAN APO AE 09366

USFOR-A CDR

24 January 2016

MEMORANDUM FOR Commander, United States Central Command, 7115 South Boundary Blvd, MacDill AFB, FL 33621-5101

SUBJECT: Request for Emergency and Extraordinary Expenses Funding

- 1. PURPOSE: USFOR-A requests \$5,790,349.00 of Emergency & Extraordinary Expenses ("Triple E") funds for the reconstruction of the heavily-damaged hospital building owned by the Government of the Islamic Republic of Afghanistan.
- 2. BACKGROUND: On 3 October 2015, U.S. combat activity in Kunduz, Afghanistan damaged a building owned by the Government of the Islamic Republic of Afghanistan (GIRoA). Spinzar Company, a state-owned enterprise, managed the building and had leased the property to Medecine Sans Frontiers ("MSF," a.k.a. Doctors Without Borders). MSF was using the building as a hospital at the time of the strike. The strike resulted in the injury or death of 273 noncombatants, as reported by MSF, and the near destruction of the compound's main facility.
- 3. USFOR-A RESPONSE: USFOR-A has identified three categories of consequence management responses: (1) condolence payments to the individuals injured or killed in the strike; (2) reconstruction of the hospital building; and (3) repair or replacement of damaged or destroyed medical equipment.
- a. Condolence payments. To date, USFOR-A has made payments to 77 representatives of the 273 wounded and deceased individuals through the Commander's Emergency Respond Program (CERP). Two more payment actions are scheduled for 24 January and 29 January 2016.
- b. Reconstruction. The hospital building is owned by the GIRoA's Ministry of Commerce and Industries (MoCI) through the state-owned Spinzar Corporation. The GIRoA has requested that USFOR-A return the facility to the same condition it was prior to the strike. The US Army Corps of Engineers (USACE) conducted a damage assessment of the Spinzar building. The assessment determined that the facility's ground floor is a total loss because it sustained heavy damage from explosions and resulting fires. The facility's basement was partially damaged and is considered repairable. The current working estimate by USACE to reconstruct the structure as a general-purpose edministrative facility is \$5,790,349.00. This estimate exceeds the amount of CERP funding available in Fiscal Year 2016.
- c. Equipment. Mr. Rahman, Deputy Minister to the MoCl, has confirmed that GIRoA had nothing of value in the building on 3 October 2015. The USFOR-A Consequence Manager has repeatedly asked MSF representatives for a listing of damaged or destroyed equipment and a cost estimate to replace or repair it. In

response, the MSF representative stated that MSF had no intention to request reimbursement or replacement of MSF's medical equipment.

- FUNDING: USFOR-A has sufficient CERP funds to make the condolence payments. USFOR-A's CERP budget does not contain sufficient funding to rebuild the GIRoA structure. USFOR-A staff could not identify another appropriate fund source sufficient to cover the costs of the building reconstruction. Accordingly, USFOR-A requests use of Triple E funds.
- 5. IMPACT IF NOT SUPPORTED: If not supported, the MoCI will lose a valuable property as a result of combat operations and the United States risks losing good will with GIRoA. Additionally, the US would remain under continued Afghan and international scrutiny. The burned-out building will remain a continued reminder of the tragic incident, fueling resentment and putting the security of the city at risk.

6. Point of contact for this memorandum is (b)(6); (b)(3):10 USC § 130b

or (b)(6): (b)(3):10 USC § 130b

Enclosures

1. USFOR-A SJA Legal Opinion

2. GIRoA Request to Reconstruct Facility

3. GIRoA Deed to Property

4. USACE Cost Estimate

USACE Assessment Report

JOHN F. CAMPBELL


poho a Cypbell

General, U.S. Army

Commander,

Resolute Support /

United States Forces-Afghanistan





Islamic Republic of Afghanistan Office of the President

Request for Reconstruction

January 23, 2016

To: General John F. Campbell, Commander, United States Porces - Afghanistan Subject: Spinzar Building Reconstruction

On 3 October 2015, United States military forces damaged a building owned by the Afghan Ministry of Commerce and Industry. Spinzar Company Kunduz, a government-controlled entity, manages the building. *Médecins Sans Frontières* conducted their operations from that building based on a lease agreement signed by Spinzar Company Kunduz.

The Government of the Islamic Republic of Afghanistan formally requests that United States Porces - Afghanistan reconstruct the building to its 2 October 2015 condition.

Mohammad

President of the Islamic Republic of Afghanistan

Kabul, Afghanistan

UNCLASSIFIED



HEADQUARTERS
UNITED STATES FORCES - AFGMANISTAN
BAGRAN, AFGMANISTAN
APO AE 00264

USFOR-A DCDR-S

23 January 2016

FOR Commander, Unites States Forces-Afghanistan, Kabul, Afghanistan APO AE 09356

SUBJECT: Request for Emergency and Extraordinary Expenses Funding

- 1. PURPOSE: USFOR-A requests \$5,790,349.00 of Emergency & Extraordinary Expenses ("Triple E") funds for the reconstruction of the heavily-damaged hospital building owned by the Government of the Islamic Republic of Afghanistan.
- 2. BACKGROUND: On 3 October 2015, U.S. combat activity in Kunduz, Afghanistan damaged a building owned by the Government of the Islamic Republic of Afghanistan (GiRoA). Spinzar Company, a state-owned enterprise, managed the building and hed leased the property to Medecina Sans Frontiers ("MSF," a.k.a. Doctors Without Borders). MSF was using the building as a hospital at the time of the strike. The strike resulted in the injury or death of 273 noncombatants and the near destruction of the facility.
- 3. USFOR-A RESPONSE: USFOR-A has identified three categories of consequence management responses: (1) condolence payments to the individuels injured or killed in the strike; (2) reconstruction of the hospital building; and (3) repair or replacement of damaged or destroyed medical equipment.
- a. Condolence payments. To date, USFOR-A has made payments to 77 representatives of the 273 wounded and deceased individuals through the Commander's Emergency Respond Program (CERP). Two more payment actions are scheduled for 24 January and 29 January 2016.
- b. Reconstruction. The hospital building is owned by the GIRoA's Ministry of Commerce and Industries (MoCI) through the state-owned Spinzar Corporation. The GIRoA has requested that USFOR-A return the facility to the same condition it was in prior to the strike. The US Army Corps of Engineers (USACE) conducted a damage assessment of the Spinzar building. The assessment determined that the facility's ground floor is a total loss because it sustained heavy damage from explosions and resulting fires. The facility's basement was partially damaged and is considered repairable. The current working estimate by USACE to reconstruct the structure as a general-purpose edministrative facility is \$5,790,349.00. This estimate exceeds the amount of CERP funding available in Fiscal Year 2016.
- c. Equipment. Mr. Rahman, Deputy Minister to the MoCl, has identified that GIRoA had nothing of value in the building on 3 October 2015. The USFOR-A Consequence Manager has repeatedly asked MSF representatives for a listing of damaged or destroyed equipment and a cost estimate to replace or repair it. In response, the MSF

UNCLASSIFIED

USFOR-A DCDR-S

SUBJECT: Request for Emergency and Extraordinary Expenses Funding

representative stated that MSF had no intention to request reimbursement or replacement of MSF's medical equipment.

- 4. FUNDING: USFOR-A has sufficient CERP funds to make the condolence payments. USFOR-A's CERP budget does not contain sufficient funding to rebuild the GIRoA structure. USFOR-A staff could not identify another appropriate fund source sufficient to cover the costs of the building reconstruction. Accordingly, USFOR-A requests use of Triple E funds.
- 5. IMPACT IF NOT SUPPORTED: If not supported, the MoCI will lose a valuable property as a result of combat operations and the United States risks losing good will with GIRoA. Additionally, the US would remain under continued Afghan and international scrutiny. The burned-out building will remain a continued reminder of the tragic incident, fueling resentment and putting the security of the city at risk.
- 6. Point of contact for this memorandum is (b)(6); (b)(3):10 USC § 130b or (b)(3):10 USC § 130: (b)(6)

Enclosures

- 1. USFOR-A SJA Legal Opinion
- GIRoA Request to Reconstruct Facility
- 3. GIRoA Deed to Property
- 4. USACE Cost Estimate
- 5. USACE Assessment Report

GEFFREY L. BANNISTER

Major General, U.S. Army Deputy Commander, Support United States Forces-Afghanistan Project Title: Kunduz Repair Hospital

Program: Emergency and Extraordinary Expense

A: Letter of Justification

B: Office of Council Legal Opinion

C: GIRoA Deed of Property / GIRoA Request for reconstruction

D: USACE cost estimate

E: USACE Afghan technical Support Team (ATST) Assessment Report




UNCLASSIFIED/FOR OFFICIAL USE ONLY



HEADQUARTERS UNITED STATES FORCES-AFGHANISTAN BAGRAM, AFGHANISTAN APO, AE 09354


PURPOSE: (Identify whe Request approval and sign BACKGROUND: (Provide Spinzar building, a General section of Commercial Supports to the Ministry of Commercial Supports to the demolished and reconstitution of Commercial Supports (Commercial Supports (Co	ide brief explication in the and industricate. It was as it Team (ATST constructed. (b)(6) Rank/Name:	taxation on backgro entity, was being lea Kunduz when it suf ries confirmed own icertained from the I) that the ground fi	ound of the perased to the Meritered significant report prepare loor of the bulk	clunge): clunge): decins Sans to battle damage. sested the facility d by the USACE ding would need FFICER: X or Name: UVAL Concurrence: (Yes/No)	SUSPENSE DATE: 29-Jan-16 heck here Wasses as: Phone: Office:
BACKGROUND: (Provide Spinzar building, a Giffrontiers (MSF) for use as The Ministry of Commercial Supports to be demolished and reconfiguration be demolished and reconfiguration (b)(6); (b)(3): 18 130b Section: (CoS) Section: (CoS)	ide brief expl IRoA owned e a hospital in te and industr tate. It was as rt Team (ATST constructed. (b)(6) 10 USC Rank/Name:	taxation on backgro- entity, was being lead Kunduz when it suf- ries confirmed owner icertained from the in- that the ground file Office: USFORALENG COORDINAT MG BANNISTER	ound of the perassed to the Medifered significant report prepare loor of the bulk ACTION O	clunge): decins Sans nt battle damage, sested the facility d by the USACE ding would need FFICER: X on Nume: Concurrence: (Yes/No)	SUSPENSE DATE: 29-Jan-16 heck here if seems as: Phone Office:
The Spirizar building, a Giffrontiers (MSF) for use as The Ministry of Commercial Support to be rebuilt to its original staffshan Technical Support to be demolished and reconfiguration of the demolished and reconfiguration (b)(6); (b)(3):1 § 130b Section: (CoS) Section: (S)S	IROA owned e a hospital in te and industr tate. It was as r Team (ATST constructed. (b)(6) 10 USC Rank/Name:	entity, was being lead Kunduz when it suffices confirmed owns in the succetained from the interest of the ground file. COORDINAT MG BANNISTER	ased to the Medifered significar ership and requireport prepare loor of the bulk ACTION O Rank: Emeil:	decins Sans Int battle damage. Lested the facility d by the USACE ding would need FFICER: X Nume: Concurrence: (Yes/Ne)	hock hore If some no. Phone: Office:
Frontiers (MSF) for use as The Ministry of Commerci be rebuilt to its original si Afghan Technical Support to be demolished and rec ORIGINATOR: Phone ((b)(6); (b)(3):1 § 130b Section: DCDR-S Section: SSS	a hospital in te and industricate. It was as it Team (ATST constructed. (b)(6) 10 USC	Kunduz when it suf- ries confirmed own- icertained from the Chat the ground fi Office: USFORATENG COORDINAT	fered significates ship and requireport prepare loor of the bulk ACTION O	rt battle damage. sested the facility d by the USACE ding would need FFICER: X or Name: DVAL Concurrence: (Yes/No)	hock hore If some no. Phone: Office:
(b)(6); (b)(3):1 § 130b Section: DCDR-S Section: CoS	Rank/Name:	COORDINAT MG BANNISTER	Rank: Emell: FION / APPRO	Nume: NAL Concurrence: (Yes/Ne)	Office:
Section: CoS Section: SS	Rank/Name:	COORDINAT MG BANNISTER	Emeil: FION / APPRO	Concurrence: (Yes/No)	
Section: DCDR-S Section: CoS Section: SJS		MG BANNISTER	TION / APPRO	Concurrence: (Yes/No)	10113 235AN
Section: CoS Section: SJS		MG BANNISTER		Concurrence: (Yes/No)	10015 235AN
Section: CoS Section: SJS			JSC § 13	(Yes/Ne)	10075 235AN
Section: SJS	(b)(6);	(b)(3):10 L	JSC § 13	30h	1 12 11
Section: J3					
Section: ja					
Section:39					
Section: SJA					
Section: JENG					
REMARKS/COMMENT	S: (Recommen	edations, Buckground, O	Option, Papers, 9	anclusions from coor	rdiantina / Approval Section):
Sir - No Hes	no provid	of the Ku	the west . where Sac	137(h)	represe Sunding Strong
USPOR-A Secretary of John Staff (SJS)					Dete:

ion's found toughter see it has











DEPARTMENT OF THE ARMY UNITED STATES ARMY CORPS OF BIGINEERS TRANSATLANTIC AFGHANISTAN DISTRICT BAGRAMARFIELD APO AE 09354-1053

CETAA-EC

MEMORANDUM FOR: USFOR-A Attn:	(b)(6)
-------------------------------	--------

SUBJECT: Rough-Order-Magnitude Estimate for Kunduz Hospital

- A site assessment of the damaged Kunduz Hospital was performed in 25 November 2015 and a final report was prepared dated 7 December 2015. Based on the results of that inspection and assessment, our office has developed the attached cost estimate in planning and budgeting for a replacement facility.
- 2. The basis of the cost estimate includes the following assumptions:
 - The existing hospital will be demolished to the slab-on-basement level and the new facility will be constructed at the same location.
 - The existing utility capacities are available to support the new facility.

Please contact the undersigned at (b)(any questions you may have.	6) or at (b)(6)	fo
	(b)(6)	
	Chief of Engineering and Construct Division	ction

Attachment

Rough Order Magnitude (ROM) Estimate

Kunduz MSF Hospital Kunduz Province, Alghamatan

23-Jen-2016 Historical Date Deta Source

CLIN No.	Description	Quantity	Unit	Unit Price	Total Amount
0001 DESIGN PROGRAM					2017
0001AA	DB Contractor Design		LB	\$220,000	\$220,000
8A2000	As-Burt Drawings	1	LS	\$6,000	\$6,000
0001AC	See Survey	2	LS	\$8,000	\$8,000
0001AD	See Security	1	LS	\$180,000	\$180,000
0002 SITE DEVELOPMENT / IMPROVE					
0002AA	Mob/Demobiasion	1	LS:	\$250,000	\$250,000
0002A8	Site DemolecryGrading	1	LS	\$300,000	\$300,000
0002AC	Water Distribution System	1	LS	\$10,000	\$10,000
0002AD	Santary Sever Correction System	1	LS	\$8,000	\$8,000
0002AE	Site Electrical Power Distribution System	1	LS	\$25,000	\$25,000
0002AF	Site Communication System	1	LS	\$10,000	\$10,000
0003 FACILITIES	3.0 3.00		-	*	
D003AA	Kunduz MSF Hospital	1	LS	\$3,450,000	\$3,450,000 See Noti
	TOTAL CONSTRUCTION				14,467,000
PEDMIP Development	% of Construction Cost		_		\$286,000
Contingency	19% of Construction Cost				\$870 050
Supervision & Administration (\$104)	7.5% of Construction Cost & Contingency				\$385,279
	Total ROM Estimate	-			30,790,349

Prepared by	(b)(6)	
Revenued By		
Approved By		

- Circuit Modes.

 *All utilities (wister, sewer, power, and communication) were assumed to be connected to the existing system.

 *No reperhappractic of assisting utility system: was considered.

 *New facility shall have the same footpoint and functionality as the existing facility.

 *Upgrade of existing facility furniture and equipment was not required.

 *No stement work was indument, except for around control.

 *Basement work was not required.

 *Existing concrete stab can be reused, as is.

 *Existing facility was 2,300 m2.

ticle 1.
* New facility 2:300 m2 at 81,500/m2

- Penod of Periomynose (PoP)

 * REP Precention & Acquision = 6 months

 * Construction Duration = 24 months

 * Total = 30 months



US Army Corps of Engineers Transatlantic Afghanistan District (TAA)



Afghan Technical Support Team (ATST)

Assessment Report

Date: 12/07/2015

Project Name& Location Medecins Sans Frontiers (MSF) Hospital Kunduz, Afghanistan Contract Number: (N/A) Inspection Discipline: Civil/Arch, Structure, Mechanic and Electric Provide by: ATST-South Team

Team Members: (b)(6)

(Structure) (Architect) (Civil) (Mechanical) (Electrical)

Reviewed By: (b)(6)

ATST- Program lead Engineer

AFGHAN TECHNICAL SUPPORT TEAM (ATST), ASSESSMENT REPORT LOG OF CONSTRUCTION - MILITARY

Table of Contents
General Narrative:
Report Summary
Each Discipline General Information
Civil/ Architecture Assessment Summery
Structural Assessment Summery
Mechanical Assessment Summery
Electrical Assessment Summery
Appendix A: Drawings (Plan and Section)
Appendix B: Civil/Architecture Assessment Photography
Appendix B-1: Structure Assessment Photography
Appendix B-II Mechanical Assessment Photography
Appendix B-III Electrical Assessment Photography
Appendix C Site photos

APGHAN TECHNICAL SUPPORT TEAM (ATST), ASSESSMENT REPORT LOG OF CONSTRUCTION - MILITARY

Medecins Sans Frontiers (MSF) Hospital Kunduz, Afghanistan

Contract No. (N/A) Inspection Date -- 11/25/2015

General Narrative:

According to the given instruction ATS team execute site inspection from the entire Medecins Sens Frontiers (MSF) Hospital of Kunduz, Afghanistan. ATS team assigned to Skatch the entire building provide the requested information.

As a result, this report prepared to present the response for the requested information. This report consist of general narrative, Report Summery of assessment from the entire structural including the utilities system of MSF hospital and existing Utilities 'connections. The Actual drawings plan indicated as appendix A; specifies the layout and dimensions of existing Hospital building, existing utilities system. As well as, Appendix B indicates Civil/Arch photography and report, Appendix B-I indicates tructure photography and Report, Appendix B-II indicates Mechanical photography and report, and Appendix B-III indicates Electrical photography and report. Appendix C; are the photos indicates the supporting photos from the entire project site. For more information refer to each discipline photography, reports and appendixes A, B-BIII and C.

Report Summary

According to the given instruction, ATS team creates this report as a final product. This report indicates mandatory information that presents (MSF) Hospital of Kunduz, the Update / actual plans, site photos, existing facilities and existing Utility condition. The following details are guides for more assistance and well understanding of this report which are:

- 1- Appendix A: Drawings of the MSF hospital plans, MSF hospital building has been divided to three sections. Each section named Wing A, wing B and Wing C, as well as, all rooms are mambered has for more facilitation of the references. Appendix indicates the actual plans contain the buildings' actual location and the existing statues of the building including the 1, dimensions and layout. Appendix A has been linked with appendix B, B-I and B-II.
- 2- Appendix B, B-I B-III describes the site photography and details including the description regarding the referenced photos, as well as the Appendix B, B-I, B-II and B-III present the four discipline s' reports (Civil/ Arch photography, Structure photography report, Mechanical photography report and Electrical photography report). Appendix B, B-I & B-II linked to Appendix A, for building's location and condition.
- 3- Appendix C is the site photos. Each discipline photos separated in folders. The discipline photos have been organized in a folder and numbered in according the rooms' numbers which are indicated on First floor plan Sheet# A-103&A-104.

AFGHAN TECHNICAL SUPPORT TEAM (ATST), ASSESSMENT REPORT LOG OF CONSTRUCTION - MILITARY

Each Discipline General Information

This information is made up for four main disciplines which are Civil/Arch. Structure, Mechanic and Electrical disciplines. Each discipline indicates the existing statues of the buildings and the related mility system of the MSF hospital. Each discipline vision has been reported individually as follow:

Civil/ Architecture Assessment Summery MSF Hospital Main Building Civil Works:

Building gutters are all burned and destroyed, additionally the building sidewalks partially damaged. As per visual inspection, the manholes related to the building are in good condition and manholes covers are partially damaged. For more information please refer to appendix B, photo # 49 & 50 and Mechanical and electrical reports for more details.

MSF Hospital Main Building Architectural Works:

As per building sketched plan, the MSF main building first floor divided into three parts (A, B and C).

MSF Hospital first floor, main building wing A & C areas:

The building Section A and C areas are completely burned out and destroyed. All walls, ceramic tile floors, roof, ceiling, PVC windows and PVC doors destroyed and burned and all of them are not repairable and operational.

Inside of the first floor building was previously divided by brick masonry partition walls that after the accident all the walls burned and destroyed.

For more information please refer to appendix B, photo # 1 through 26 and sketched drawing, sheet A-102 (Kunduz, MSF Hospital Buildings Wings Classification Plan.

First floor wing B area, south side:

The room's concrete walls and roof including gypsum suspended ceilings damaged and the ceramic floors are in good condition but full of debris.

PVC doors and windows of building wing B rooms damaged and glasses broken.

For more information please refer to appendix 9, photo # 27 through 36 and sketched drawing, sheet A-102 (Kunduz, MSF Hospital Buildings Wings Classification Plan.

Building Besement:

There are two basements in this building located in the east and west sides.

East Side basement:

AFGHAN TECHNICAL SUPPORT TEAM (ATST), ASSESSMENT REPORT LOG OF CONSTRUCTION - MILITARY

The concrete stair of the east basessent is partially damaged. No door was installed in the basement and only PVC windows installed.

The concrete plaster and paint of the east basement partially demaged and is repairable. For more information please refer to appendix B, photo # 37 through 42 and sketched drawing, sheet A-103 (Kunduz, MSF Hospital Basement Floor Plan).

West Side basement:

No door was installed in the besement and only PVC windows installed.

The paint of the east basement partially damaged and is repairable. Moreover, the roof of the east basement damaged by rocket. For more information please refer to appendix B, photo #43 through 48 and sketched drawing, sheet A-103 (Kunduz, MSF Hospital Basement Floor Plan).

Structural Assessment Summery

MSF Hospital is located Kunduz province, Afghanistan. According to MSF Coordinator statements /information; "Due to Bombing/ rocket with heavy explosion and fire; MSF hospital has been totally burned". Due to many explosions and fire the hospital building has been damaged and burned. This report presents the current condition/ statues of the MSF building.

Structurally, the MSF building modeled one story with two separate basements which are located on the East and West side of the hospital. For more facilitation, the building has been divided into three parts and named Wing A (East section) Wing B (Middle section) and Wing C (West section), each rooms of the building numbered individually refer to appendix A see plans A-103&: A-104.

Due to the fire and explosions impacts; the entire roof of this building which was constructed by wooden truss, Roof sheets and fall ceiling has been damaged. But section B which is different with section A&C in structure is partially damaged. This section has concrete frame structure.

The most damages occurred into section A&C. Both section walls have been constructed by brick masonry wall. Mostly, the exterior and interior walls damaged.

- Exterior finishing and Roof trues with sheeting, insulation, purlins and roof rafters from
 absolutely damaged and not usable. For more information rafer to appendix B-1 see photos I-36.
- Interior finishing: the ceilings, walls, floors, alebs, doors, windows including the existing hospital
 stuff and equipment has been burned and damaged. Section B which is located at the middle of
 the other wings less damaged. But, most damages occurred on section A and C. For more
 information refer to appendix B-I see photo# 37-78.
- According to size visual inspection, all doors and windows are made of PVC. With different sizes
 (1.35X1.4, 1.2x1, 27, 1.2x1.5...) all windows and doors has been burned or damaged. For more
 information refer to appendix B-I see structural photography.
- Interior finishing: suspend ceiling, concrete/ ceremic floors, walls are plastered. For more information refer to appendix B-1 see photo# 1-4, 35, 36, 66, 67, 70&72.

AFGHAN TECHNICAL SUPPORT TEAM (ATST), ASSESSMENT REPORT LOG OF CONSTRUCTION - MILITARY

- Also, the explosion has effected on other facilities which are located all around the hospital.
 Some existing facilities have been damaged and needs repairing. For more information refer to appendix B-I see photost 8, 11, 28, 35& 36.
- Structure photography indicates the exterior perimeter walls and building condition, including the
 interior condition. It indicates structure statues as well. For more information refer to appendix BI see photography.

Mechanical Assessment Summery

During inspection of Kunduz hospital that we have conducted on the mechanical system, which is included: Water, Sewer, Heating and vertilation system of the MSF Hospital. Due to the explosions and fire, the entire mechanical system which was operable into inside and outside of the hospital was damaged. In the building, which has been destroyed had central heating system, consist of two boiler, two pump, one diesel tank that were located into basement; and radiators, supply pipes system and return pipe system that located inside the building's rooms. With regard to, water system, there were three water storage tanks inside the hospital area, which was pumping the water all through the building by booster pump and the building's sewer systems were all directed toward to three leach fields, which were located around the building. The following are more information about the mechanical system.

Heating system

In Kunduz Hospital, almost everything related to central heating system inside the rooms (radiators and pipes) were destroyed and need reconstruction, except two boilers, two pump and a diesel tank which were located in the basement. Refer to Appendix E Mechanical supporting Photo report, photosil 1, 2, 3, 4, 5, 6, 7 and 8.

Water System

There were three water storage tanks (two located on the ground and another elevated water storage) inside the hospital area, which are pumping the water all through building by booster pump. Furthermore, all expose pipes, fixtures and sanitary materials (water closet, lavatory, sink and water heater) inside the building were damaged; all of them must be reconstructed and underground pipes need to be tested. Refer to Appendix E Mechanical supporting Photo report, photoss! 9-20.

Sewer System

The building's sewer systems were all directed toward four leach fields, which were located around the building; and all the expose pipes (Above the ground pipes) were destroyed being inside or outside the building. Furthermore, underground pipes are not visible and tests such as, pressured test, leakage test, stack tests are required to determine the problem. Refer to Appendix E Mechanical supporting Photo report, photos# 21-24.

Ventilation

In the Kunduz hospital (duraged building) during our inspection and observation there were ventilation duct with louver in three different location of the building. Furthermore, all three ventilation ducts with louvers have been destroyed. Refer to Appendix E Mechanical supporting Photo report, photos# 24-28.

APGHAN TECHNICAL SUPPORT TEAM (ATST), ASSESSMENT REPORT LOG OF CONSTRUCTION - MILITARY

Electrical Assessment Summery

All electrical systems have been damaged, burned out and not operational in MSF Kunduz Hospital main building.

Location: MSF Kunduz Hospital main building

Photo information: All electrical systems have been damaged, burned out and not operational for more detail see Appendix III photos! 01 up to 12.

Location: MSF Kunduz Hospital main building basements

Photo information: The basement of the building is divided into two parts; both basements have been located on East and West sides of the Hospital Wing A & C in accordance to the building plan Sheet # A-102. The west site basement electrical system have not been installed from the beginning and in the east site electrical system have been installed but now it is not operational, electrical wiring is in poor conditions and their connection with the power supply interrupted for more detail see Appendix III photo# 13 up to 16.

Location: MSF Kunduz Hospital


Photo information: The electrical cable that feeds the building has been cut in outside of the building see photo# 17 and 18. Electrical cables in the manholes are not verified. Due to damage of manholes it was not specific that which cable is feeding the building. Moreover, This Hospital has been powered by four Generators and one stepdown transformer which is feed from city power. Generators and transformer are located in south site of main building, the distance between main building and Generators; transformer is about 85 Meters for more detail see Appendix III photo# 17 up to 24 in electrical photography section.


APPENDIX A Architecture Drawings Plans and section





KUNDUZ, MSF HOSPITAL EXISTING AERIAL MAP


APPENDIX A. KEY PLAN MP-001














APPENDIX B Civil and Architecture Assessment photography




First Floor and basement MSF Hospital Building


Kunduz MSF Hospital Exterior Photos



Kunduz MNF Hospital: Exterior photos information: General view, building front.



Kunduz MSF Hospital: Exterior photos Information, Building North



Kunduz MSF Hospital: Exterior photos information: Building East elevation



Kunduz MNF Hospital: Exterior photos Information: entrance




MSF Hospital, Building # 505 Interior Photos







Kunduz MSF Hospital:

information: The building Section, wing A & C areas are complettly burned out and destroyed. All wells, ceramic tile floors, roof, ceiling, PVC windows and PVC doors destroyed and burned.




Hospital main building wing A






Appendix B




Appendix B






Konduz MSF Hospital:


Information. The inside of the first floor building was previously divided by brick masonry partition walls that after the accident all the walls burned and destroyed.



Hospital main building wing A


Wing/ section B






Kunduz MSF Hospital, Main Entrance:


Information: No wall, caramic tiles floor, roof, calling, PVC windows and PVC doors are repairable and operational because all damaged and burned.




Appendix B




Appendix B







Kunduz MSF Hospital:

Information. The building Section A and C areas are completely burned get and destroyed. All walls, ceremic tile floors, roof, celling, PVC windows and PVC doors destroyed and burned.







Appendix B



Appendix B




Appendix B






Kunduz MSF Hospital:

First floor wing 8 area, south side: The room's concrete wall and roof are damaged. Moreover gypsum suspended ceilings damaged and the ceramic floors are in good conditing but full of debris.




Hospital main building wing B




Hospital main building wing B







Kunduz MSF Hospital:

First floor wing 8 area, south side: Brick mesonry walls damaged.




Hospital main building wing B






Kunduz MSF Hospital:

First floor wing 8 area, south side: The room's concrete wall and roof are damaged. Moreover gypsum suspended ceilings damaged and the ceramic floors are in good condition but full of debris.





Hospital main building wing B

Appendix B




Appendix B






Kunduz MSF Hospital, East Balement: The concrete stair of the east besement is partially damaged.




Hospital main building East Basement






Kunduz MSF Hospital, East Basement: No door was installed in the basement doors and only PVC windows installed without glasses.




Appendix B






Kinduz MSF Hospital, Cast Basement: The plaster and paint of the east basement partially damaged and is repairable.




Hospital main building East Basement





Kunduz MSF Hospital, West Basement: No door was installed in the basement doors and only PVC windows installed.



Hospital main building West Basement




Physically



Photo a 46



in order 17



Phote # 18

Kunduz MSF Hospital. West Hasement: The point of the east basement partially damaged and is repairable. Additionally the roof of the east basement was damaged by rocket.






Photo # 50


Great Lands

Kandinz MSF Hospital, Manholes:

The manholes related to the building are in good condition and manholes covers are partially damaged.

APPENDIX B-I


Structure
Assessment photography



Apparently, one rocket/bomb hit at the North West corner, all roof sheets, doors and windows have been burned.




a scation: MSF Hospital, Wing C (Sheet# 103), North side view Kepota: East section constructed by brick masoury with wooden beams and roof sheeting. Apparently, one rocket/ bomb hit at the North West corner, all roof sheets, doors and windows have been burned.





Focation: MSF Hospital, Wing A, B&C (Sheet# 103), from North side view
Report: Report: another rocket/ bomb hit at the middle of this section, all roof sheets' beams, doors and windows have been burned. Roof sheets are fall down.





ocution; MSF Hospital, Wing C (Sheet# 103), North side view with Existing facilities.

Perion: another rocket/ bomb hit at the middle of this section, all roof sheets' beams, doors and windows have been burned. As well as, boundary wall's iron sheets with entrance gate including the Gard rooms which are located onto the North side of hospital need repairing.



i ocation: Section A (Sheet# 103), North east corner Report: Due to the fire, all roof's wooden beams, doors, windows, existing equipment has been burned. Most part of the roof sheeting is collapse and other parts are over hang.




I.ocation: Section A (Sheet # 103), MSF Hospital, East side.
Report: Due to the fire, all roof's wooden beams, doors, windows, existing equipment has been burned.
Most part of the roof sheeting is collapse and other



t.ocation: Section A (Sheet# 103), Sidewalks, existing facilities (connexes).

Report: Due to the Bombing, the existing facilities which are located next to the hospital including the side walk on side are damaged as well.



Location: Hospital, Room#107, Shoet#A-103
Report: Another rocket/bomb sign, it caused damaged and all existing equipment plus the roof beams, doors windows has been burned due to the fire.



Report: Due to explosion all roof sheets with doors and windows has been damaged needs repairing. There are some damaged parts and cracks visible onto the walls on east side exterior walls.



Location: East view/Elevation, Section B (Sheet# 103)
Report: Due to explosion all roof sheets with doors and
windows has been damaged needs repairing. There are
some damaged parts and cracks visible onto the walls
on east side exterior walls.



Report: Due to explosion all roof sheets with doors and windows has been damaged needs repairing. There are some damaged parts and cracks visible onto the walls on east side exterior walls.




Location: East view/Elevation, Section B (Sheet# 103)
Report: Due to explosion all roof sheets with doors and
windows has been damaged needs repairing. There are
some damaged parts and cracks visible onto the walls
on east side exterior walls.



Due to explosion and fire all roof sheets with wooden beams, doors and windows has been damaged. There are some damaged parts and cracks visible onto the walls on South side exterior walls. Physically, the perimeter wall stable.



Location: South view/Elev., Wing C (Sheet# 103)
Report. Due to explosion and fire all roof sheets with
doors and windows has been damaged. There are some
damaged parts and cracks visible onto the walls on
South side exterior walls. Physically, the perimeter
wall stable.



recations South view/Elev., Wing C (Sheet# 103)

style ** Due to explosion and fire all roof sheets with
doors and windows has been damaged. There are
some damaged parts and cracks visible onto the walls
on South side exterior walls. Physically; the
perimeter wall of this side seems stable.



Report Due to explosion and fire all roof sheets with doors and windows has been damaged. There are some damaged parts and cracks visible onto the walls on South side exterior walls. Physically; the perimeter wall of this side seems stable.



A period: South view/Elev., Wing B (Sheet# 103)


**LineXII: Due to explosion all roof sheets with doors and windows have been damaged. Physically; the perimeter wall of this side seems stable.



Location: South view/Elev., Wing B (Sheet# 103)
Report: Due to explosion all roof sheets with doors and windows have been damaged. This facility, roof and wall covers has been damaged totally.



t recation: South view/Elev., Wing B (Sheet# 103)
Report: Due to explosion all roof sheets with doors and windows have been damaged. Framing system is still repairable.



Location: South view/Elev., Wing B (Sheet# 103)
Report Due to explosion all roof sheets with doors and windows have been damaged. Framing system is still repairable.



Report Due to explosion and fire all roof sheets including the wooden beams with doors and windows have been damaged.



Location: South view/Elev., Wing A (Sheet# 103)
Report. Due to explosion and fire all roof sheets
including the wooden beams with doors and windows
have been damaged.



Location: South view/Elev., Wing A (Sheet# 103)
Seport: Due to explosion and fire all roof truss including
the roof sheets with doors and windows has been
damaged. There are some damaged parts and cracks
visible onto the walls on South side exterior walls of this
section. There are some damage parts of perimeter wall.



Location: South view/Elev., Wing A (Sheet# 103), entrance side walk.

Report: Entrance side walk has been damaged, as well as the connexes which are located onto the South side of hospital partially damaged and need repairing.



Report: West view/Elev., Wing C (Sheet# 103)
Report: Due to explosion and fire all roof truss including the roof sheets with doors and windows has been damaged. There are some damaged parts and cracks visible onto the walls on West perimeter wall of hospital.



Location: Orld 34
Keport: One rocket/ bomb, hit at the North West corner, all roof sheets, doors and windows have been burned.



Caution; West view/Elev., Wing C (Sheet# 103)

Basement Stair

Separa: Brick masonry stair landing is partially damaged.




l ocation: West view/Elev., Wing C (Sheet# 103)

Report: Brick masonry stair landing is partially damaged



Report: Due to explosion and fire all roof truss including the roof sheets, wooden beams, with doors and windows has been damaged and burned. There are some damaged parts and cracks visible onto the walls on West perimeter wall of hospital.

the second second of the engine equipment the remains a mention to the remains the second of the engine of the second of the engine of the second of the sec



Location: West view/Elev., Wing B (Sheet# 103)
Report: Due to explosion and fire all roof truss including
the roof sheets, wooden beams, with doors and windows
has been damaged and burned. There are some damaged
parts and cracks visible onto the walls on West perimeter
wall of hospital.



Report: Due to explosion and fire all roof truss including the roof sheets, wooden beams, with doors and windows has been damaged and burned. There are some damaged parts and cracks visible onto the walls on West perimeter wall of hospital.



i ocation: West view/Elev., Wing B (Sheet# 103)
Report: Due to explosion and fire all roof truss including
the roof sheets, wooden beams, with doors and windows
has been damaged and burned. There are some damaged
parts and cracks visible onto the walls on West perimeter
wall of hospital.

INTERIOR PHOTOS, ROOMS AND WALLS, SECTION B




Cocation: MSF Hospital, Wing B, North entrance, Room #128,129,101

he nort: Structurally the building has been constructed with brick masonry and wooden beams with roof sheeting tall ceiling, wall plaster, floor ceramic/concrete are visible to this wing.




Location: MSF Hospital, Wing B, North entrance, Room #128,129,101

Report: Structurally the building has been constructed with brick masonry and wooden beams with roof sheeting. Fall ceiling, wall plaster, floor commic/concrete are visible in this wing.




time: MSF hospital building has been sketched in accordance to the site. The plan has been divided to three parts (Wing A, Wing B and Wing C) each wing has been inspected and reported separately. The most damages occurred on section A and C which are totally destroyed; wing B is partially damaged. Even though, wing B shouted by rocket/bomb as well but this part structurally constructed differently forms the two other parts (Wing A& wing C). Wing B has been made of concrete frame and slab with brick masonry walls. For more info, refer to floor plan sketch (Sheet# A-102)



water: MSF Hospital, Wing B. Room #148

school Due to the rocket/ bomb impact the exterior wall has been damaged.




Appendix B




Examine MSF Hospital, Wing B, Room #150 Support Due to the rocket/ bomb impact the roof slab and floor has been damaged.



Location: MSF Hospital, Wing B, Room #150 Report: Due to the rocket/ bomb impact the roof slab and floor has been damaged.



Securion: MSF Hospital, Wing B, Room #150
Report: Due to the rocket/bomb impact the roof slab and floor has been damaged.



releasion; MSF Hospital, Wing B, Room #151


 ${\rm Region}($ Due to the rocket/bomb impact the roof slab walls and floor has been damaged.




i exciton: MSF Hospital, Wing B, Room #155
Memory Due to the rocket/ bomb impact the fall ceiling has been damaged.




Location: MSF Hospital, Wing B, Room #155
Report: Due to the rocket/ bomb impact the fall ceiling has been damaged.




Report: Due to the rocket/ bomb impact the roof slab walls and floor has been damaged.





Local MSF Hospital, Wing B. Room #161

Name of Due to the rocket/ bomb impact exterior wall with the door lintel has been damaged.




i ocation: MSF Hospital, Wing B, Room #162


Report These photos indicate the wall, roof, ceiling and floor flaishing in wing/section B as well as it indicates the heating system.


Wing/Section A




Cocarion: MSF Hospital, Wing A, Room #116
Report: Due to the rocket/ bomb impact the entire wing/section has been damaged, all roof trusses, roof sheeting, wall with the doors and windows has been damaged.








Appendix B




Appendix B



Appendix 8

Page 23 of 29



Location: MSF Hospital, Wing A. Room #148

Report summary Section A: Due to the rocket/bomb impact the exterior and interior walls have been damaged. Physically the walls stand and soom stable; but, the impacts and explosion and fire has effect on the entire structure. Therefore, the most damages has been occurred in the entire section A. all existing tools, stuff/equipment that was inside this section have been damaged and burned.






Location: MSF Hospital, Wing C, Room #138 Report: Due to the fire and rocket/ bomb impact the roof truss with sheets has been damaged.





Location: MSF Hospital, Wing C, Room #138 Report: Due to the fire and rocket/ bomb impact the roof trus with sheets has been damaged.



Succetees: MSF Hospital, Wing C, Room #138

Remain Due to the fire and rocket/ bomb impact the roof truss with sheets has been damaged. The entire section C physically damaged. Roof truss including the sheeting, doors, windows, existing equipment and stuff has been damaged and burned. Nothing is reparable. The most damages occurred on this section.







i.ocation: MSF Hospital, Wing C, Room #180 Seport: Due to the rocked bomb impact the entire structure and existing facilities have been damaged.



Location: MSF Hospital, Wing C, Room #180 Report: Due to the rocket/ bomb impact the entire existing facilities have been damaged.







t occurrent MSF Hospital, West side Basemen Report: Due to the rocket/ bomb impact the stair of this basement has been damaged. This basement has been constructed by brick masonry.

Location: MSF Hospital, West side Basemen Report: Due to the rocket/ bomb impact the stair of this besement has been damaged. This basement has been constructed by brick masonry

AST SIDE BASEMENT



Location: MSF Hospital, East side Basemen Report: Due to the rocket/ bomb impact the roof slab of the basement has been damaged. This basement has concrete frame structure.




Southern MSF Hospital, East side Basemen Report: Due to the rocket/ bomb impact the roof slab of the basement has been damaged. Some cracks visible around the beams and girder nest to the columns



Location: MSF Hospital, East side Basemen Report: Due to the rocket/ bomb impact the roof slab of the basement has been damaged. Some cracks visible around the beams and girder nest to the


APPENDIX B-II

Mechanical
Assessment photography



* ocation: Kunduz Hospital Basement heating system

effects information. The photos above show mechanical central heating systems, which are located in the basement, consist of two boiler, one diesel tank, pumps, supply pipe and return pipes.




is content. Kunduz Hospital Ground Floor Heating System

**Hospital Administration in Kunduz Hospital, almost everything related to central heating system inside the rooms (radiators, supply pipes and return pipes) were destroyed.




* station: Kunduz Hospital Area

There were three water storage tanks (two located on the ground and another elevated water storage) inside the hospital area, which are pumping the water all through building by booster pump.



Location: Kunduz Hospital

The HVAC air diffusers, air grills, air dampers are damaged due to fire inside the hangar therefore the sentioned mechanical HVAC systems are not functional for ventilation of hangar.




Location: Kunduz MSF Hospital


Photo #15


Photo information: There are two HVAC units located outside the hangar each HVAC unit have one supply duct and one return duct for ventilation of inside the hangar, but due to fire inside the hangar smoke is influenced into the units therefore the units needs to maintenance. The mentioned units functionality is could not verify because there was no power.

Photo #16











water system and fixtures

The automotive Almost all expose pipes, fixtures, water heater and sanitary materials (water closet, lavatory and sink) inside the building were destroyed; all of them must be reconstructed



l ocation; Kunduz hospital Sewer, North and West sides.
Photo information: All the expose pipes (Above the ground pipes) were destroyed being inside or outside the building (damaged building).



sation Kunduz hospital ventilation system, North Elev.

These information. In the Kunduz hospital during our inspection and observation there were ventilation duct with louver in three different location of the building. Furthermore, all three ventilation ducts with louvers have been destroyed.

APPENDIX B-III


Electrical
Assessment photography



Photo # 93



Photo # 02



1.046 115



Photo # 04

💎 🕬 MSF Kunduz Hospital milin building


it is a machinate to All electrical systems have been damaged, burned out and not operational.



Cable tray fall down

Musica # H#





 $Pl_{\rm eff}$ o \pm 07



Photo # 08

constroit MSF Kunduz Hospital main building

Photo information. All electrical systems have been damaged, burned out and not operational.





 $\Omega_{E_{\alpha}(g,1,\mathcal{L})} g$



Photo 239




their air

Photo #12

A Date of MSF Kunduz Hospital main building

where the transfer All electrical systems have been damaged, burned out and not operational.


impeador (i)





Pareto #13

Photo #14



Acolo 215

Photo 5 6

is content MSF Kunduz Hospital main building basements

The basement of the building is divided into two parts. The one is located at the west sit of the building and the other one is located at the east sit of the building. The west site basement electrical system have not been installed and in the east site electrical system have been installed but now it is not operational, electrical wiring is in poor conditions and their connection with the power supply interrupted.





Photo #17

Photo #18



MSF Kunduz Hospital

The electrical cable that feeds the building has been cut in outside of the building see photo# 17 and 18. Electrical cables in the manholes are not verified and due to damage of manholes it was not specific that which cable is feeding the building. For more information please see photos# 19 and 20.



Photo -2

Photo #22





Photo #21

Photo #24

- scarces; MSF Kunduz Hospital, Generator Room& step down transformer

Production This Hospital has been powered by four Generators and one stepdown transformer which is feed from city power. Generators and transformer are located in south site of main building, the distance between main building and Generators, transformer is about 85 Meters.

APPENDIX C Site Photos